



Office Of The Executive Engineer,
BCD, Construction Division, Darbhanga.

NIQ

QUATATION NO - 03 / YEAR-2015-16

N/C

Sealed quotations are invited by the undersigned from the registered suppliers /Forms/ Agencies/Any Reg. Contractor for the work of **Supply of submersible Pump set and other accessories in A Type Qrt.(14 Unit & 2 Block), B Type Qrt.(16 Unit & 4 Block) at Benipur Darbhanga** on dated 15.06.2015 up to 3.00 PM as noted below with all complete job. The quotations shall be opened on dated 15.06.2015 at 3.30 PM. in the Office of the Executive Engineer, BCD, Construction Division, Darbhanga.

S. No	Description	Quantity	Unit
1	Transportation of Ring Machine with necessary equipment & Materials to work site.	6	NO.
2	Providing all equipments & labour and drilling in all kinds of soil (soft/hard) sand and sand stone by reverse circulation method 300/250mm dia bore hole for insertion of 125mm dia UPVC Casing pipe/ slotted pipe, UPVC Screen pipe for installation. 300mm dia 0.0 m to 30.0m 250mm dia 30.0m to 60.0m 250mm dia 60.0m to 90.0m	180 180 180	M M M
3	Providing all equipments & labour for lowering 125mm dia UPVC Casing pipe/50mm slotted UPVC ribbed screen pipe as per confirming to the available strata (slotted pipe/Screen pipe)are to be lowered in water bearing aquifer and as per direction of E/I at site and else where casing pipe will be lowered. 100mm dia. UPVC Pipe. 50 mm dia. PVC Pipe. 50 mm dia. PVC Pipe.	180 180 180	M M M
4	S/F/F the flowing GI fitting of approved make and specification at work site all complete job. 100mm dia. Centre guide. 50 mm dia. Well plug. 100 mm dia. Clamp. 100 mm dia. Cap	24 6 6 6	NOS NO. NO. NO.
5	Supplying 3mm to 8mm well size of dalbhungarh quarry pea gravel including washing flushing and filling properly in the T/W including transportation staking all complete up to the depth of 10m below GL. in annular space between bore hole and 125mm dia pipe uniformly as direction of E/I.	24	M3
6	Supplying all materials equipments & labour to seal T/W up to the depth of 10m below GL.by sticky clay to prevent contamination from surface all complete job as per direction E/I.	6	Each
7	Supplying of tools equipments & labour for flushing , washing & developing the T/W to give cline & clean water upto 20 hours complete and all complete job as per direction E/I.	6	Each
8	S/F/F 1 HP Submersible motor pump of a approved make with all necessary fitting having 32mm dia delivery pipe and required size of cable and panel board with all cost of labour material and equipment and T & P all complete job.	6	Each
9	S/E/F Syntex water Tank capacity of 1000 Ltr. of approved quality.	6	NOS.

Time of Completion:- 15 Days

Conditions:-

- 1 The Rate quoted by the quotationer must include all Taxes and VAT.
- 2 The work shall be carried out as per the specification mentioned above.
- 3 IT/VAT details must be attached with quotation.
- 4 Rate quoted should be supported with analysis of rate in details.

Sdr
Executive Engineer,
BCD, Construction Division, Darbhanga.

Memo No...../ Darbhanga. Date.....

Copy forwarded to the Director, Information and Public Relation Deptt. Bihar, Patna with CD of

NTQ and five hard copies for publication.

Encl.- As above.

Sd/-
Executive Engineer,
BCD, Construction Division, Darbhanga.

Memo No. 970...../ Darbhanga. Date 23.05.15

Copy forwarded to the S.E. Building Circle, Darbhanga/D.M. Darbhanga/A.E. (B) No. 1&2,
Darbhanga/ A.E.(B) Henipur/Cashier,BCD Darbhanga/ DAO, BCD Darbhanga for information and necessary action..

Him
Executive Engineer,
BCD, Construction Division, Darbhanga.